

**ANNEXURE-A**

<b>S.NO</b>	<b>DESCRIPTION</b>	<b>QTY</b>	<b>Unit</b>	<b>UNIT RATE( RS)</b>
<b>01.</b>	Laying & dressing of 3-1/2 core Cx 300 sq mm aluminium armoured PVC sheath cables in cable tray either located above ground or inside RCC cable trenches or through floor conduit including supply and fixing of aluminium clamps, aluminium cable tags and hardware.	1000	Mtr	
<b>02.</b>	Fixing of indoor LED light including its cable dressing and connection.	10	No	
<b>03.</b>	Fixing of double compression cable gland for above said cable.	2	No	
<b>04.</b>	End Termination of above said cable ( Gland size 3 ")	2	No	
<b>05.</b>	Laying dressing and welding work of G I Strip size 25 x 6 MM	80	Mtr	
<b>06.</b>	Installation work of earthing pad on cable tray.	2	No	