




Punjab Alkalies & Chemicals Limited

Regd. Office : S.C.O. 125-127, Sector 17-B, Chandigarh - 160 017 (INDIA)

Phone : 0172-4072508-568, E- mail : info@punjabalkalies.com Fax : 0172-2704797

PACL: PUR: 2018 CIN : L24119CH1975PLC003607, Website : www.punjabalkalies.com Date: 09.11.2018



Sub: Tender enquiry for Electrical job works related to installation of new waste air blower and sodium hypo circulation pump for sodium hypo tower no -03 in Unit-2 at our works at Naya Nangal.

Dear Sir,

With reference to above subject sealed offers are invited from reputed parties to carry out the above jobs. Other details and terms and conditions are as below:-

1. **SCOPE OF WORK** : Scope of work will be as per annexure-A enclosed herewith. Price Bid to be submitted in separate envelop marked as price bid
2. **Last date of Submission of offers**:- 22.11.2018
3. **Offer validity**:-Offer should be valid for a period of 90 days.
4. **Earnest money**:-interest parties should deposit EMD of Rs. 5000.00 by way of demand draft favouring –PUNJAB ALKLAIES & CHEMICALS LIMITED, payable at Chandigarh in a separate envelop marked EMD.
5. **Security Deposit**:- The successful contractor will have to deposit security of Rs. 6600.00. Security deposit will be released on satisfactory completion of job.
6. **Others**:-
 - a) Material like cable, cable gland, structural steel and GI strip etc will be provided by us as free issue.
 - b) Contractor will provide all safety gadgets etc as and wherever required for completion of the job.
 - c) After completion of job contractor will deposit the scrap with stores dep't and clear the site. Scrap deposit slip should be attached with the invoice for clearance.
 - d) All tools and tackles, scaffolding (Steel) material, chain pulley blocks, ropes, Grinders or any other tools/machinery required for completion of the job will be arranged by the contractor.
 - e) Electricity connection and water if required shall be provided by PACL.
 - f) Contractor will take proper care while using the material so that there is no wastage of material issued by PACL.



- g) Contractor will insure their workmen with proper insurance policy as per Govt rules and submit a copy of the same with our HR Deptt.
- h) Contractor will have to comply with all statutory obligations as applicable.

7. **PAYMENT TERMS:** - Payment will be released within 30 days of submission of bills after completion of job.

8. **OTHER TERMS & CONDITIONS:**

- a) Taxes: - GST as applicable will be paid extra.
- b) Income tax: - income tax if applicable will be deducted at source.
- c) Completion time: Work to be completed in 30 days' time
- d) Quantities mentioned in scope of work may vary+/-10%. Payment will be made for actual work done as verified by our site in charge.
- e) **Billing:** - Bill to be raised in favour of following address:-

PUNJAB ALKALIES & CHEMICALS LIMITED,

NANGAL UNA ROAD, NAYA NANGAL-(PB) - 140126.

GST NO 03AAACP9915E1ZN

9. **ARBITRATION CLAUSE:**

In all cases of dispute of disagreement between the purchaser and the supplier as to any matter arising out of or relating to this purchase order/work order whether such dispute or disagreement shall arise during the continuance of the work order/purchase order regarding interpretation of this Work Order of any Clause or Clauses thereof or upon or after the termination hereof and provided no understanding between the parties can be reached for the settlement of the difference, shall be referred to the sole arbitrator of the Managing Director of Punjab Alkalies & Chemicals Ltd or any officer appointed by him on his behalf in accordance with Arbitration and Conciliation Act, 1996. or any Statutory modifications or substitute thereof and all the provisions of that Act, so far as are applicable or of any of them for the time being in force shall apply to every reference hereunder.

The award given by such Arbitrator shall be final conclusive and binding upon the parties to this work order. The arbitrator may from time to time, with consent of parties, enlarge the time for making or publishing the award. The arbitration proceedings shall be held at Chandigarh.

Notwithstanding any pending reference to arbitration both parties shall precede with the execution of their commitments under the purchase order/work order until the arbitration award is known, unless the question of such continuance is a subject matter of such proceedings.

11. **LAW AND ITS JURISDICTION**

The work order shall be governed by the laws of Govt. of India in force from time to time and shall be deemed to have been concluded in the Union Territory of Chandigarh. All suits and proceedings shall be subject to jurisdiction of the courts at Chandigarh only.



We reserve the right to accept/reject any or all offers without assigning any reason thereof.

Thanking you,

Yours faithfully

For Punjab Alkalies & Chemicals Ltd.

K K GOYAL

Deputy Manager (Purchase)



ANNEXURE

SCOPE OF WORK FOR INSTALLATION OF NEW WASTE AIR BLOWER NO.-03, AND SOUDIUM HYPO CIRCULATION PUMP FOR SOUDIUM HYPO CIRCULATION TOWER -03 IN UNIT-02.

| S.No. | Item | Quantity | Unit Rate (Rs.) | Amount (Rs.) |
|-------|---|-----------|-----------------|--------------|
| 1. | Laying and dressing of 3 Cx 25Sq.MM Aluminium armoured PVC Sheath cables in cable tray either located above ground or inside RCC cable trenches or through floor conduit including supply and fixing of aluminium clamps, aluminium cable tags and hardware | 300 Mtr's | | |
| 2. | Laying and dressing of 3 Cx 25Sq.MM Aluminium armoured PVC Sheath cables in cable tray either located above ground or inside RCC cable trenches or through floor conduit including supply and fixing of aluminium clamps, aluminium cable tags and hardware | 200 Mtr's | | |
| 3. | Double compression cable gland for 3Cx 25 Sq.MM Aluminum armoured PVC Sheath cables | 04 no's | | |
| 4. | End termination of 3Cx 25 Sq.MM Aluminum armoured PVC Sheath cable. | 4 No's | | |
| 5. | End termination of 1Cx16 Sq.MM Aluminum armoured PVC Sheath earth cable. | 40 no's | | |
| 6. | Laying and dressing of 6Cx 1.5 Sq.MM Copper armoured PVC Sheath cables in cable tray either located above ground or inside RCC cable trenches or through floor conduit including supply and fixing of aluminium clamps, aluminium cable tags and hardware | 300 Mtrs. | | |

pqcl

| | | | | |
|--------------|---|----------|--|--|
| | Double compression cable gland for 6Cx 1.5 Sq.MM Copper armoured PVC Sheath cables(Gland Size ¾ inch) | 04 no's | | |
| 8. | Installation for Local control station for on/off the motors in field. | 02 no's | | |
| 9. | Construction of Earthing Pit including material and material mention as under:- 1.) G.I. plate 600x600. 2.) G.I Strip 50x6. 3.) G.I. Pipe 1 1/2 inch. 4.) Cast iron Cover 450x450MM 5.) Depth of earth pit is 15 feet. 6.) Masonry work with material like as sand ,bricks and cement for construction work of chamber. | 04 no's | | |
| 10. | Laying ,dressing and welding work work of G.I. Strip, size 25x6mm. | 80 Mtr's | | |
| 11. | Material are as below for Fabrication of New/Damaged cable trays:- MS channel 50x 50 x 6 MM MS angle 50 x 50 x 6 MM and MS Flat 25 x 6 MM/50x6MM | 4MT | | |
| 12. | Installation work of Earthing Pad on cable tray | 04 no's | | |
| TOTAL | | | | |